

SHEET 00

Overview & Spec Sheet

What we are building, out of what, to what tolerance.

Eight shade bays, each 50 ft x 30 ft, tiled into a 3 x 3 grid with one bay left open. Overall footprint is roughly 150 ft x 90 ft. Adjacent bays SHARE a wall - that wall gets built once, not twice.

SPECIFICATION

Bay size	50 ft x 30 ft (8 bays)
Overall footprint	approx. 150 ft x 90 ft
Pole height	10 ft
Grid spacing	10 ft - one post every 10 ft along every wall
Frame	1 in x 10 ft galvanized EMT conduit
Joints	Maker Pipe 1 in connectors: 2-way (wall end), 3-way (corner / inline), 4-way (wall junction), 5-way (interior cross)
Pole base	Maker Pipe flange, one per vertical
Bracing	1 in x 15 ft ratchet tie-down, 500 lb WLL
Ground anchor	1/2 in x 18 in hex lag bolt + fender washer or climbing hanger
Anchor offset	7 ft out from the pole base (approx. 55 deg from ground)
Design wind	approx. 90 mph

PARTS COUNT (WHOLE CAMP)

Derived from the current layout. Confirm against the live bill of materials in Build Week > Shade Schema before ordering or staging.

Vertical poles	approx. 81
Top rails	approx. 88 (approx. 169 EMT sticks total)
3-way connectors	approx. 71 (corners and inline)
4-way connectors	approx. 6 (wall junctions)
5-way connectors	approx. 4 (interior crosses)
Base flanges	approx. 81
Ratchet straps	approx. 90
Lag bolt anchors	approx. 28

SCHEMA COLOUR CODE

- Blue = 3-way connector (corner or inline pole).
- Green = 4-way connector (wall junction / T).
- Purple = 5-way connector (interior cross).
- Orange = ratchet strap, pyramid leg or ground anchor.
- Amber = pole shared by two bays. Built once, by the owning bay.
- Gray = EMT pole and top rail.

Read the schema, not your memory. Every pole, connector and strap on this build is drawn in Build Week > Shade Schema (3D and 2D Plan). Print the 2D plan and carry it.