

SHEET 01

Site Layout & Grid Marking

Nothing gets assembled until the whole footprint is flagged and square.

TOOLS

Measuring wheel, 100 ft tape, marking flags, chalk or marking paint, the printed 2D plan.

PROCEDURE

- 1 Pull the baselines**
Run the 50 ft and 30 ft baselines off the camp frontage line with the measuring wheel. Flag all four corners of the bay.
- 2 Square the rectangle**
Use the 3-4-5 rule at full scale (30-40-50 ft) or check both diagonals. On a 50 x 30 bay both diagonals must read 58 ft 4 in and must match each other within 1 in.
- 3 Flag every post point**
Place a flag every 10 ft along all four walls: 6 points on each 50 ft wall, 4 on each 30 ft wall. An isolated bay has 16 posts.
- 4 Resolve shared walls**
Where two bays meet, the wall is built once. Amber poles in the schema belong to the bay that owns them - do not flag or stage a second set.
- 5 Flag the whole complex before building**
Walk and flag every bay first. Cumulative measuring error is the number one reason the last wall will not close.

Check your work against the printed plan before a single pole leaves the staging pile. Moving flags is free. Moving a strapped 50 ft wall is not.